

Town of Ridgefield
Office of the Purchasing Manager

Addendum Number 1

Bid Number 24-06

Request for Quotes

Scotts Ridge School Fence

To All Bidders:

The Scope of Work for the above referenced bid is changed as follows;

Section reading;

- Furnish and install new black vinyl coated chain link fence according to specifications below. Fence will be installed reusing the existing pole hardware. All wire gauges specified indicate wire gauge before coating.
 - Install 675 linear feet (LF) of 4', 9 ga. black vinyl coated chain link fence.
 - Install 275 LF of 6', 9 ga. black vinyl coated chain link fence.
 - Install 375 LF of 12', 6 ga. black vinyl coated chain link fence.
 - Tie in new 12' fence with existing upper fence sections and tie in loose sections of upper 12' fence.
 - Install new 4', 9 ga. black vinyl coated chain link fence on all gates and adjust gates as needed.

Now reads;

- Furnish and install new black vinyl coated chain link fence according to specifications below. Fence will be installed reusing the existing pole hardware.
 - Install 675 linear feet (LF) of 4', **8 ga. extruded and bonded** black vinyl coated chain link fence.
 - Install 275 LF of 6', **8 ga. extruded and bonded** black vinyl coated chain link fence.
 - Install 375 LF of 12', 6 ga. black vinyl coated chain link fence.
 - Tie in new 12' fence with existing upper fence sections and tie in loose sections of upper 12' fence.
 - Install new 4', **8 ga. extruded and bonded** black vinyl coated chain link fence on all gates and adjust gates as needed.