

Barrack Hill Refuge Eagle Project

Lisa van Gompel


Introduction



My name is Lisa van Gompel, I'm 17-years-old and I'm a rising senior at RHS. I'm part of Troop 19 which is the only and first female Troop in town. I achieved the rank of Life recently and I am working on my Eagle Project at Barrack Hill Refuge.

Project Description

- Placing 5 bog bridges on a part of the trail of Barrack Hill Refuge which will make it easier to walk the trail.
- There are multiple areas that need to be replaced with Bog Bridges but it would be too much to do it as one Eagle Project.
- The area I will cover is about 40 feet long.



Benefits

- Will make it easier to walk since it creates a stable underground
- People won't have to walk in the mud when it rained.
- Children of the neighbourhood will be able to play safer and easier on the trail.



Current situation

Materials

- 4" x 4" x 8' Lumber
- 2" x 10" x 16' Lumber
- 4" screws

Tools*


- Saw
- Screwdrivers
- Drill
- Drill Bits
- Clamps

Supplies*

- Sanding paper
- First aid kit
- water bottles,
- Food
- hand sanitizer
- Garbage bags
- Face masks
- Safety goggles
- Dust masks
- Sunblock
- infrared thermometer

* Not in cost estimate for Conservation Committee. Required in Eagle Workbook.

Sketches



Timeline and Total costs

Total costs

Ridgefield Supply Company
29 Prospect Street
Ridgefield, CT 06877
Telephone: 203-438-2626
Fax: 203-438-3817

Quotation
Quote No **138320**
Quote Date 07/23/2020
Expiration Date 8/6/2020

Cash Customer
Invoice Address
CT

Delivery Address
CT

Customer
Your Ref
Taken By
Sales Rep

CASH
WPEL- EAGLE SCOUT
Zach Orbanic
HOUSE ACCOUNT

Contact Number LISA VAN GOMPEL Contact Number

Page 1 of 1

Line	Product Code	Description	Qty/Footage	Price	Per	Total
1	PT040408	4X4X8 TREATED SYP #1 4/8	4 ea	20.51	ea	82.04
2	PT021016	2X10X16 TREATED SYP #1 5/16	5 ea	40.47	ea	202.35
3	TX1400CP	SCORPION #10 X 4" XT CERAMIC COATED STAR DRIVE SCREW 150PC - 725	1 ea	26.09	ea	26.09

Total Amount	\$310.48
Sales Tax	\$19.72
Quotation Total	\$330.20

Timeline

- Start in middle of August (pending material availability)
- Finish at the end of August

Thank you for your time!